

Form of Tender
26-5708 Burnham Street Watermain Replacement
Township of Selwyn



Total Tender Price			Total Price
Subtotal for Division 1 - Site Preparation and Earthworks			\$0.00
Subtotal for Division 2 - Removals			\$0.00
Subtotal for Division 3 - Sanitary Sewer			\$0.00
Subtotal for Division 5 - Watermain			\$0.00
Subtotal for Division 6 - Restoration and Roadworks			\$0.00
Subtotal for Division 9 - Provisional			\$0.00
Subtotal			\$0.00
	H.S.T	13.00%	\$0.00
Total Tender Amount			\$0.00

Division 1 - Site Preparation and Earthworks							
Item	SP	OPSS	Description of Work	Qty.	Unit	Unit Price	Total Price
101	SPW 01		Bonding	1	LS		\$0.00
102	SPW 02	OPSS 805	Mobilization and Demobilization	1	LS		\$0.00
103	SPW 03		Pre-Condition Survey	1	LS		\$0.00
104	SPW 03		Post-Condition Survey (Provisional)	5	Ea.		\$0.00
105	SP 706	OPSS 709	Temporary Traffic Control	1	LS		\$0.00
106	SP 206	OPSS 206	Earth Excavation, Surplus	180.0	m³		\$0.00
Subtotal for Division 1 - Site Preparation and Earthworks							\$0.00

Division 2 - Removals							
Item	SP	OPSS	Description of Work	Qty.	Unit	Unit Price	Total Price
201		OPSS 510	Cutting Existing Pavement	23.5	m		\$0.00
202		OPSS 510	Removal of Asphalt Pavement (Full depth)	370.0	m²		\$0.00
203		OPSS 510	Removal of Concrete Sidewalk	30.0	m²		\$0.00
204		OPSS 510	Removal of Concrete Curb	17.5	m		\$0.00
205		OPSS 510	Removal of Pipes and Culverts	57.0	m		\$0.00
Subtotal for Division 2 - Removals							\$0.00

Division 3 - Sanitary Sewer							
Item	SP	OPSS	Description of Work	Qty.	Unit	Unit Price	Total Price
301		OPSS 410	150mm DR 35 PVC Sanitary Service Connection	5.0	m		\$0.00
302	SPW 04	OPSS 409	Pre- and Post Construction CCTV Inspection (including flushing)	210.0	m		\$0.00
Subtotal for Division 3 - Sanitary Sewer							\$0.00

Form of Tender
26-5708 Burnham Street Watermain Replacement
Township of Selwyn



Division 5 - Watermain							
Item	SP	Spec. No	Description of Work	Qty.	Unit	Unit Price	Total Price
501	SP 441	OPSS 441	150mm C900 PVC Watermain	58.0	m		\$0.00
502	SP 441	OPSS 441	150mm Gate Valve	2	Ea.		\$0.00
503	SP 441	OPSS 441	19mm Service Connection	15.5	m		\$0.00
504	SP 441	OPSS 441	32mm Service Connection	6.5	m		\$0.00
505	SP 441	OPSS 441	50mm Service Connection	3.5	m		\$0.00
506	SP 441	OPSS 441	Service Connection Appurtenance Sets	4	Ea.		\$0.00
507	SP 493	OPSS 493	Temporary Potable Water Supply Services	1	LS		\$0.00
508	SP 441		Watermain Testing and Commissioning	1	LS		\$0.00
509		OPSS 441	150mm C900 PVC Fire Line (including Anchor Tee and Valve, Cap and Standpipe)	1	LS		\$0.00
Subtotal for Division 5 - Watermain							\$0.00

Division 6 - Restoration and Roadworks							
Item	SP	OPSS	Description of Work	Qty.	Unit	Unit Price	Total Price
601	SP 314	OPSS 314	Granular B - Type 1, Road Subbase (300mm Depth)	205.0	m ²		\$0.00
602	SP 314	OPSS 314	Granular A, Road Base (150mm Depth)	260.0	m ²		\$0.00
603		OPSS 312	Asphalt Curb	17.5	m		\$0.00
604		OPSS 408	Structure Adjustments to Finished Grade	3	Ea.		\$0.00
605	SP 310	OPSS 310	Base Asphalt (50mm HL8)	370.0	m ²		\$0.00
606	SP 310	OPSS 310	Temporary Asphalt Sidewalk (50mm HL8)	30.0	m ²		\$0.00
Subtotal for Division 6 - Restoration and Roadworks							\$0.00

Division 9 - Provisional							
Item	SP	OPSS	Description of Work	Qty.	Unit	Unit Price	Total Price
901	SP 1605	OPSS 1605	Pipe Insulation (Provisional)	25.0	m		\$0.00
902	SPW 07		Handling, Removal, and Disposal of Designated Substances (Provisional)	15.0	m		\$0.00
903		OPSS 407	300mm dia. Concrete Storm Sewer (Provisional)	20.0	m		\$0.00
Subtotal for Division 9 - Provisional							\$0.00